



Notes:

1. All dimensions in millimetres unless otherwise stated.
2. Materials and construction to be in accordance with B.S. 1722 part 7
3. All timber and pressure treatment to be in accordance with the specification.
4. When specified, painting to be in accordance with the specification.
5. All posts to be set in 300 dia. hole. Posts may be driven in suitable ground with the permission of the Project Manager.
6. Posts set in 300 dia. augered hole should be backfilled with suitable excavated material being well compacted as filling proceeds. If excavated material is unacceptable for backfilling post holes shall, at the direction of the Engineer, be backfilled to at least half their depth with Concrete Class GEN2.



COUNTY HALL
 Pegs Lane
 Hertford, Herts
 SG13 8DN
 Phone: 01992 555555

Revisions

- A - AUG 23 UPDATED DETAIL
- B -
- C -

Drawing Title

NAILED WOODEN POST
 AND TWO RAIL FENCE

Dwg No: HST/0300/004

Scale at A4 : N.T.S.

Drawn RD	Approved JE	Revised
Checked STM	Date JULY '11	Date