



- NOTES:**
1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS STATED OTHERWISE.
  2. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH HST/1100/002.
  3. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH HST/1100/043.
  4. FOR PRECAST CONCRETE FLAGS SIZES AND TYPE OF BOND DIMENSIONS REFER TO THE WORKS ORDER.
  5. PRECAST CONCRETE FLAGS SHALL BE LAID IN ACCORDANCE WITH THE RECOMMENDATIONS OF BS 7533 PART 4.
  6. WHERE PRECAST CONCRETE FLAGS ARE USED IN AREAS LIKELY TO BE TRAFFICKED, THEY SHALL BE OF REINFORCED CONSTRUCTION APPROVED BY THE OVERSEEING ORGANISATION.
  7. MORTAR SHALL BE DESIGNATION (ii) OR (iii). CLAUSE 2404 AS PER SPECIFICATION OF HIGHWAY WORKS.
  8. ALL MORTAR POINTING SHALL BE COLOUR MATCHED TO THE FLAG.
  9. MORTAR PIGMENT SHALL COMPLY WITH BS EN 12878.
  10. SUBBASE SHALL BE ONE OF THE MATERIALS COMPLYING WITH CLAUSE 803 OR CLAUSE 891AR, 892AR, 893AR OR 894AR, AS SPECIFIED IN THE WORKS INFORMATION.
  11. WHEN EXCAVATING TO FOOTWAY FORMATION LEVEL, THE FULL DEPTH OF EXISTING MATERIAL, INCLUDING TOPSOIL SHALL BE REMOVED, ANY ADDITIONAL DEPTH OF EXCAVATION RESULTING FROM THIS SHALL BE BACKFILLED WITH SUBBASE AS NOTE 10.



COUNTY HALL  
 Pegs Lane  
 Hertford, Herts  
 SG13 8DN  
 Phone: 01992 555555

Revisions		
A -	FEB 20	REVISED DETAIL
B -		
C -		

Drawing Title

FOOTWAY TYPE 5  
 PRECAST CONCRETE FLAGS FOOTWAY  
 (FOR FLAGS 450mm SQUARE OR LARGER)

Dwg No: HST/1100/026		
Scale at A4 : 1:10		
Drawn	Approved	Revised
YS	HH	A
Checked	Date	Date
KK	JULY 11	FEB 20